

Countertop and Backsplash Projects

Measure: Countertop, Backsplash and Sink Base cabinet

Look at existing conditions: check to see if cabinets have shims

Check the floor if it looks level

Measure and take photos of INSIDE sink base cabinet for new sink

Look under sink cabinet for: Garbage Disposal, Hot & Cold Accessory, Valves Take photos of each

If necessary, have Electrician and Plumber come to see the job otherwise take photos to show them the job requirements for estimating.

What to tell the Customer:

New Valves are installed with every job if we are disconnecting and reconnecting the plumbing

Backsplash to be removed before countertop template

Cabinets need to be leveled

Ask if they need a new sink, faucet and accessories

****Have Christine from Plimpton & Hills to price****

Plumbing to be disconnected, as close as possible to template date

Electrical to be disconnected, as close as possible to template date

12" countertop overhang for stools is standard, anything over that will require a support bracket

If the countertop needs to be removed it will be done at a different time before the template.

We schedule removal, template and installation and will notify the customer the time window approximately 24 hours before the date

All new plumbing items to be on site for template: Sink, Faucet, soap dispenser, hot water dispenser etc.

Steps for new countertop:

Backsplash to be removed

Level all cabinetry

Plumbing to be disconnected

Electrical to be disconnected if electric stove

All new items to be on site for template: Sink, Faucet, soap dispenser, hot water dispenser etc.

Removal of countertop (usually by Genrose and at a separate time)

Template by stone company (usually by Genrose) Cabinets to be level

Installation of new countertop

Installation of new backsplash

Grouting the following day

Plumber to reconnect sink faucet and accessories

Electrician to reconnect stove and other electrical items

Painting if applicable to start

