

# SCOPE OF WORK

## Bathroom Gut Renovation

Guilford, CT | Residential

---

**Property Address:**

**Homeowner Name:**

**Contractor Name:**

**CT License #:**

**Date:**

**Estimated Project Value:** \$

## 1. PROJECT OVERVIEW

This Scope of Work ("SOW") describes the full gut renovation of one (1) bathroom in a single-family residential property located in Guilford, Connecticut. The project includes complete demolition of the existing bathroom to studs, new plumbing rough-in and finish work, new electrical rough-in and finish work, waterproofing, cement backer board installation, tile installation (floor and shower surround), radiant heated floor system installation, fixture installation, drywall and paint, and all associated finish work.

All fixtures — tub/shower, toilet, and vanity/sink — shall be replaced at the same locations unless otherwise noted in an approved Change Order. All work shall be performed in compliance with the Connecticut State Building Code, the Town of Guilford building requirements, the National Electrical Code (NEC), and all applicable plumbing and electrical codes.

The Contractor shall furnish all labor, equipment, tools, and supervision required to complete the work described herein unless otherwise specified. Materials and fixtures shall be provided as designated in Section 5 (Materials & Fixtures) of this document.

## 2. PERMITS & COMPLIANCE

The Contractor shall be responsible for the following:

- Obtaining a **Building Permit** through the Town of Guilford Online Permit Portal.
- Obtaining a separate **Plumbing Permit** for all plumbing work.
- Obtaining a separate **Electrical Permit** for all electrical work.
- Scheduling and passing all required inspections, including rough-in and final inspections for framing, plumbing, and electrical work.
- Obtaining a **Certificate of Occupancy** (or Certificate of Completion, as applicable) upon project completion.
- All work must comply with the **Connecticut State Building Code** and all applicable local, state, and federal regulations.
- Contractor must provide a valid Connecticut Home Improvement Contractor registration (HIC license) and a current certificate of liability insurance prior to commencement of work.

**Note — Homeowner Obligation:** Homeowner shall obtain the required **Zoning Permit** from the Guilford Zoning Department prior to the Contractor's building permit application. The Zoning Permit is a prerequisite for the building permit.

# 3. DETAILED SCOPE OF WORK

## 3.1 Demolition

- Protect all adjacent areas (hallway, adjoining rooms) with poly sheeting and floor protection before demolition begins.
- Disconnect and remove all existing fixtures: tub/shower unit, toilet, vanity, sink, mirror, and all associated hardware.
- Remove all existing wall tile and floor tile throughout the bathroom.
- Remove all existing drywall and/or plaster to expose wall studs on all walls.
- Remove existing flooring down to the subfloor.
- Remove all existing light fixtures, electrical outlets, switches, and exhaust fan.
- Cap all plumbing supply and drain lines during the demolition phase.
- De-energize and cap all electrical circuits during the demolition phase.
- Inspect subfloor for water damage, rot, or mold. Report all findings to Homeowner in writing before proceeding.
- Inspect framing members and floor joists. Report any structural concerns to Homeowner in writing before proceeding.
- If the home pre-dates 1980: test for asbestos-containing materials and lead-based paint prior to demolition. If hazardous materials are found, remediation shall be performed by a licensed abatement contractor at a separate cost not included in this SOW.
- Remove and properly dispose of all demolition debris. Dumpster rental and hauling are included in this scope of work.

## 3.2 Rough Plumbing

*All plumbing work shall be performed by a CT-licensed plumber.*

- Install new hot and cold water supply lines (copper or PEX, as permitted by code) to all fixture locations.
- Install new drain/waste/vent (DWV) piping as required by the approved layout.
- Relocate or add supply and drain lines per the approved plan, as necessary.
- Install shower valve rough-in with a **pressure-balancing / anti-scald valve** as required by the Connecticut State Plumbing Code.
- Set toilet flange at the proper height for the new finished floor elevation.
- Install proper venting for each fixture in accordance with the plumbing code.
- Pressure test all supply lines prior to rough plumbing inspection.
- Schedule and pass **rough plumbing inspection**.

## 3.3 Rough Electrical

*All electrical work shall be performed by a CT-licensed electrician.*

- Install dedicated 20-amp circuit(s) for the bathroom per NEC requirements.
- Install electrical boxes for all light fixtures (vanity, overhead/recessed, and shower-rated fixture locations).
- Install wiring for **GFCI-protected outlets** (required within 3 feet of any water source per NEC).
- Install wiring for the exhaust fan. Fan shall be ducted to the building exterior — **not** terminated into the attic space.

- Install a dedicated circuit and wiring for the electric radiant floor heating system.
- Install wiring for the heated floor thermostat/control unit.
- Install switch boxes for all lighting controls and fan controls.
- Schedule and pass **rough electrical inspection**.

### 3.4 Framing & Structural

- Reframe any walls modified per the approved layout (if applicable).
- Install wood blocking in wall framing for: towel bars, grab bars, accessories, wall-mounted vanity (if applicable), and shower fixture mounting points.
- Reinforce floor joists if required to support new tub, shower base, or other heavy fixtures.
- Frame shower niche(s) per the approved plan.
- Frame shower curb (if applicable).
- Schedule and pass **rough framing inspection** (if structural work is performed).

### 3.5 Waterproofing

- Install cement backer board (or approved equivalent substrate) on all walls in wet and shower areas.
- Apply a code-compliant waterproof membrane system on all shower walls, shower floor, curb, seat, and niche surfaces.
- Waterproof the shower pan/floor with proper slope to the drain (minimum  $\frac{1}{4}$  inch per foot to drain).
- Perform a **flood test** of the shower pan. Document results in writing and provide to Homeowner before proceeding with tile installation.

### 3.6 Tile Installation

- Install wall tile in the shower/tub surround per the approved tile layout and design.
- Install floor tile throughout the bathroom per the approved tile layout.
- Install accent tile, border tile, and niche tile as specified in the approved design.
- Install tile on shower curb and shower seat (if applicable).
- Grout all tile joints with **mold-resistant grout**.
- Seal all grout lines per grout manufacturer's recommendations.
- Install tile trim pieces, edge pieces, and transition strips at all exposed tile edges and floor transitions.

### 3.7 Heated Floor System

- Install electric radiant floor heating mat per manufacturer's specifications and installation guidelines.
- Perform **continuity and resistance test** of the heating mat before tile installation. Document test results.
- Install floor tile over the heating mat system using manufacturer-approved thin-set mortar.
- Install wall-mounted thermostat/control unit for the heated floor system.

### 3.8 Drywall, Paint & Finish Surfaces

- Install **moisture-resistant drywall** (green board or equivalent) on all non-tiled wall surfaces and ceiling.
- Tape, mud, and sand all drywall to a smooth finish (Level 4 minimum).
- Prime all drywall surfaces with appropriate primer.

- Apply two (2) coats of **moisture-resistant paint** in Homeowner-selected color. Finish shall be satin or semi-gloss.
- Install ceiling finish (paint or moisture-resistant material as specified).

### **3.9 Fixture Installation**

- Install tub/shower unit or shower base per manufacturer's specifications.
- Install shower door (frameless, framed, or sliding as specified) or shower curtain rod, as applicable.
- Install toilet with wax ring (or wax-free seal) and secure to flange.
- Install vanity cabinet and countertop.
- Install sink and faucet assembly.
- Install all shower trim: valve handle, showerhead, diverter, and tub spout (if combination unit).
- Connect all supply and drain lines to installed fixtures. Test all connections for leaks.
- Install pop-up drains and overflow assemblies.

### **3.10 Electrical Finish**

*All electrical finish work shall be performed by a CT-licensed electrician.*

- Install all light fixtures: vanity light bar, overhead/recessed lights, and shower-rated light fixture.
- Install GFCI outlet(s) with cover plates.
- Install exhaust fan unit and connect ductwork to the exterior wall or roof termination point.
- Install all switches, dimmers, and cover plates.

- Install heated floor thermostat and commission the radiant floor system.

### 3.11 Final Details & Accessories

- Install mirror or medicine cabinet.
- Install all bathroom accessories: towel bars, robe hooks, toilet paper holder, soap dish/niche accessories.
- Apply **mold-resistant silicone caulk** at all fixture-to-wall and fixture-to-floor joints.
- Apply silicone caulk at all tub/shower-to-tile joints and changes of plane.
- Install baseboard and trim (painted wood or PVC as specified).
- Install door hardware (if bathroom door is replaced).
- Perform a thorough **final cleaning** of the entire bathroom, including all fixtures, tile, glass, and surfaces.

## 4. HOMEOWNER RESPONSIBILITIES

The Homeowner shall be responsible for the following:

- Obtain the **Zoning Permit** from the Guilford Zoning Department prior to the Contractor's building permit application.
- Select and approve all finish materials (tile, fixtures, paint colors, grout color, accessories) in a timely manner to avoid schedule delays. Material selections shall be finalized no later than **two (2) weeks** prior to the scheduled start of the relevant phase.



- Provide the Contractor with reasonable access to the work area and the property during the project duration.
- Make timely decisions on any Change Orders or unforeseen conditions reported by the Contractor.
- Clear all personal items from the bathroom and immediate work area prior to the demolition start date.

## 5. MATERIALS & FIXTURES

The following table shall be completed prior to contract execution. All materials and fixtures are subject to Homeowner approval. Substitutions require written approval from both parties.

| Item                | Specification / Model | Supplier | Provided By                                                        | Status |
|---------------------|-----------------------|----------|--------------------------------------------------------------------|--------|
| Tub/Shower Unit     |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Shower Door         |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Toilet              |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Vanity Cabinet      |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Vanity Countertop   |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Sink                |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Faucet (Sink)       |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Shower Valve & Trim |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Showerhead          |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |

| Item                       | Specification / Model | Supplier | Provided By                                                        | Status |
|----------------------------|-----------------------|----------|--------------------------------------------------------------------|--------|
| Floor Tile                 |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Wall / Shower Tile         |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Accent / Niche Tile        |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Grout (Color)              |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Heated Floor Mat System    |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Heated Floor Thermostat    |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Exhaust Fan                |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Vanity Light Fixture       |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Overhead / Recessed Lights |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Shower Light               |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Mirror / Medicine Cabinet  |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Paint Color & Brand        |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Towel Bars / Accessories   |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |
| Grab Bars                  |                       |          | <input type="checkbox"/> Owner <input type="checkbox"/> Contractor |        |

## 6. INSPECTION SCHEDULE

The Contractor shall schedule all required inspections with the Town of Guilford Building Department. Results shall be documented below and copies of all inspection reports provided to the Homeowner.

| Inspection Type          | Scheduled Date | Inspector | Result (Pass/Fail) | Notes |
|--------------------------|----------------|-----------|--------------------|-------|
| Rough Framing            |                |           |                    |       |
| Rough Plumbing           |                |           |                    |       |
| Rough Electrical         |                |           |                    |       |
| Final Building           |                |           |                    |       |
| Final Plumbing           |                |           |                    |       |
| Final Electrical         |                |           |                    |       |
| Certificate of Occupancy |                |           |                    |       |

## 7. PROJECT TIMELINE

The following timeline represents the Contractor's estimated schedule. Actual dates are subject to inspection scheduling, material lead times, and unforeseen conditions. The Contractor shall notify the Homeowner promptly of any anticipated schedule changes.

| Phase   | Description | Estimated Duration | Start Date | End Date |
|---------|-------------|--------------------|------------|----------|
| Phase 1 | Demolition  | 2-3 days           |            |          |

| <b>Phase</b>                    | <b>Description</b>                 | <b>Estimated Duration</b> | <b>Start Date</b> | <b>End Date</b> |
|---------------------------------|------------------------------------|---------------------------|-------------------|-----------------|
| <b>Phase 2</b>                  | Rough Plumbing & Electrical        | 3-5 days                  |                   |                 |
| <b>Phase 3</b>                  | Inspections (Rough-In)             | 1-3 days*                 |                   |                 |
| <b>Phase 4</b>                  | Waterproofing & Backer Board       | 2-3 days                  |                   |                 |
| <b>Phase 5</b>                  | Tile Installation                  | 4-6 days                  |                   |                 |
| <b>Phase 6</b>                  | Drywall, Paint & Heated Floor      | 3-4 days                  |                   |                 |
| <b>Phase 7</b>                  | Fixture Installation & Finish Work | 3-4 days                  |                   |                 |
| <b>Phase 8</b>                  | Final Inspections & Punch List     | 2-3 days                  |                   |                 |
| <b>TOTAL ESTIMATED DURATION</b> | <b>4-6 weeks</b>                   |                           |                   |                 |

*\* Phase 3 duration depends on Town of Guilford inspection scheduling availability.*

## 8. PAYMENT SCHEDULE

Payments shall be made according to the following milestone schedule. Amounts shall be agreed upon by both parties prior to contract execution and entered below.

| #            | Milestone                                      | Percentage     | Amount (\$) | Date Paid |
|--------------|------------------------------------------------|----------------|-------------|-----------|
| 1            | Deposit — upon contract signing                | ____%          | \$_____     |           |
| 2            | After demolition complete                      | ____%          | \$_____     |           |
| 3            | After rough-in inspections pass                | ____%          | \$_____     |           |
| 4            | After tile installation complete               | ____%          | \$_____     |           |
| 5            | Upon substantial completion / final inspection | ____%          | \$_____     |           |
| 6            | Final payment — after punch list complete      | ____%          | \$_____     |           |
| <b>TOTAL</b> | <b>100%</b>                                    | <b>\$_____</b> |             |           |

**Note:** Final payment shall be released upon completion of all punch list items and issuance of the Certificate of Occupancy (or Certificate of Completion) by the Town of Guilford Building Department.

## 9. CHANGE ORDER PROCEDURE

Any changes to this Scope of Work — including additions, deletions, or modifications to the work described herein — must be documented in a written **Change Order** signed by both the Homeowner and the Contractor **before** any additional or modified work begins.

Each Change Order shall include the following information:

- A clear description of the changed, added, or deleted work.
- The cost impact of the change (increase or decrease to the contract price).
- The schedule impact of the change (additional days, if any).
- Signatures of both the Homeowner and the Contractor, with the date of approval.

No verbal agreements regarding changes to the scope, cost, or schedule shall be binding. The Contractor shall not proceed with any changed work until the Change Order has been fully executed by both parties.

## 10. WARRANTY

The Contractor shall provide the following warranties:

- **Workmanship Warranty:** A minimum of one (1) year warranty on all workmanship, commencing on the date of substantial completion or issuance of the Certificate of Occupancy, whichever is later.
- **Manufacturer Warranties:** The Contractor shall pass through all manufacturer warranties on fixtures, materials, and equipment to the Homeowner.
- **Documentation:** The Contractor shall provide the Homeowner with all warranty documentation, product manuals, care and maintenance instructions, and proof of registration (where applicable) at project completion.

The workmanship warranty covers defects in labor and installation, including but not limited to: tile cracking due to improper installation, plumbing leaks at connections made by the Contractor, grout failure, and

waterproofing failures. The warranty does not cover damage caused by Homeowner misuse, normal wear and tear, or acts of nature.

## **SIGNATURES**

By signing below, both parties acknowledge that they have read, understand, and agree to the terms and conditions set forth in this Scope of Work. This document, together with any attached exhibits, schedules, or referenced Change Orders, constitutes the full agreement between the parties regarding the scope of renovation work described herein.

### **HOMEOWNER**

Signature:

Date:

Printed Name:

### **CONTRACTOR**

Signature:

Date:

Printed Name:

Company:

CT License #:

Scope of Work — Bathroom Gut Renovation | Guilford, CT | Residential